

PROJECT:	CHMS Replacement of 3 AHU COILS AND CONDENSERS
CONTRACT:	202101-03 CHMS Replacement of 3 AHU COILS AND CONDENSERS
DESCRIPTION:	Demolition of existing Trane AHU coils and condensers, associated piping as required

ADDENDUM #2 TO ADJUST PROJECT DESCRIPTION TO MATCH SCOPE OF WORK, WHICH REMAINS THE SAME

Attachment #1

SCOPE OF WORK

**Scope of work will include but not be limited to:
(Bid must include price breakdown of the following)**

- Project design work
- Demolition of existing Trane AHU coils and condensers, associated piping as required
- Equipment demolition and delivery rigging
- Disconnect all necessary electrical and sheet metal
- Recover all refrigerant
- Install new Trane condensers/coils into positions
- Reconnect sheet metal, electrical and insulation to air handlers modifying wherever necessary
- Replace all necessary refrigerant
- Pressurize, leak check and charge pipes per manufacturer specs
- Install all necessary temp controls
- Integrate all controls to existing BMS
- System start up and commissioning work
- Test/inspect equipment
- Equipment/project warranty service
- Disposal (provide dumpster) any additional removal/installation charge not included above, freight/delivery charges and inspection fees etc
- ALL WORK TO BE COMPLETED BY JUNE 30, 2021.