Attachment A3.3 Specifications

INDEX TO SPECIAL PROVISIONS (continued)

| <u>P</u> | age No. | <u>Item</u> |
|----------|---------|----------------------------------------------------------------------|
| | 116 | NOTICE TO CONTRACTOR – FLOOD CONTINGENCY PLAN REQUIREMENTS |
| | 116 | NOTICE TO CONTRACTOR – NO STORAGE OR STAGING OF MATERIALS |
| | | WITHIN FLOODPLAIN WITHOUT REVIEW AND |
| | | WRITTEN APPROVAL |
| | 116 | NOTICE TO CONTRACTOR – STANDARD DRAWINGS |
| | 116 | INFORMATION TO BIDDERS |
| | 117 | NOTICE TO CONTRACTOR – BIDRIGGING AND / OR FRAUDS |
| | 117 | NOTICE TO CONTRACTOR – SUPERVISION AND INSPECTION |
| | 117 | NOTICE TO CONTRACTOR – PUBLIC UTILITIES |
| | 117 | NOTICE TO CONTRACTOR – PROTECTION OF EXISTING UTILITIES |
| | 117 | NOTICE TO CONTRACTOR – UTILITY COORDINATION |
| | 119 | NOTICE TO CONTRACTOR – NCHRP REPORT 350 REQUIREMENTS FOR |
| | | WORK ZONE TRAFFIC CONTROL DEVICES |
| | 119 | NOTICE TO CONTRACTOR – TRAFFIC DRUMS AND CONES |
| | 119 | NOTICE TO CONTRACTOR – VEHICLE EMISSIONS |
| | | |
| | 120 | Item # 0090060 A - BRIDGE PLAQUE |
| | 121 | Item # 0202491 A - REMOVAL OF GRANITE STONE CURBING |
| | 122 | Item # 0402903 A - BRICK PAVING |
| | 127 | Item # 0406267 A - MILLING OF HMA (0-4 INCHES) |
| | 131 | Item # 0511203 A - POLYVINYL CHLORIDE PLASTIC PIPE WEEPHOLES |
| | 132 | Item # 0511211 A - CONSTRUCT WEEP DRAINS |
| | 133 | Item # 0514981 A - PRECAST CONCRETE ARCHITECTURAL PANELS(SITE No. 1) |
| | 135 | Item # 0601196 A - VARIABLE DEPTH PATCH |
| | 140 | Item # 0601231 A - LIGHTWEIGHT CONCRETE |
| | 141 | Item # 0601604 A - ASPHALTIC PLUG EXPANSION JOINT SYSTEM |
| | 144 | Item # 0602910 A - DRILLING DOWELS AND GROUTING DOWELS |
| | 146 | Item # 0603736 A - SPECIAL PAINTING TREATMENT |
| | 147 | Item # 0603893 A - TEMPORARY SLAB SUPPORT |
| | 148 | Item # 0605000 A - DIMENSION STONE MASONRY |
| | 149 | Item # 0609030 A- REPOINT MORTAR JOINTS |
| Rev 1 | 150 | Item # 0703029 A - ROUNDED STONE RIPRAP |
| | 151 | Item # 0822001 A - TEMPORARY PRECAST CONCRETE BARRIER CURB |
| | 152 | Item # 0822005 A - TEMPORARY PRECAST CONCRETE BARRIER CURB |
| | | (STRUCTURE) |
| | 152 | Item # 0822006 A – RELOCATE TEMPORARY PRECAST CONCRETE BARRIER |
| | | CURB (STRUCTURE) |
| | 157 | Item # 0904136 A – REMOVAL OF EXISTING METAL BRIDGE RAIL |
| | 158 | Item # 0921001 A - CONCRETE SIDEWALK |
| | 159 | Item # 0921036 A - RETRO-FIT DETECTABLE WARNING STRIP |
| | 160 | Item # 0969060 A - CONSTRUCTION FIELD OFFICE, SMALL |
| | 168 | Item # 0970006 A – TRAFFICPERSON(MUNICIPAL POLICE OFFICER) |
| | 171 | Item # 0971001 A - MAINTENANCE AND PROTECTION OF TRAFFIC |
| | 184 | Item # 0975002 A – MOBILIZATION |
| | 185 | Item # 0979003 A - CONSTRUCTION BARRICADE TYPE III |
| Rev 1 | 185A | Item # 0999002 A - DISPOSAL OF BUILDINGS |
| | 186 | Item # 1003906 A - REMOVE LIGHT STANDARD |
| | 187 | Item # 1008138 A - 4" POLYVINYL CHLORIDE CONDUIT IN STRUCTURE |
| | 187 | Item # 1008143 A - 4" POLYVINYL CHLORIDE CONDUIT UNDER ROADWAY |
| | 187 | Item # 1008144 A - 5" POLYVINYL CHLORIDE CONDUIT UNDER ROADWAY |

ITEM #0999002A – DISPOSAL OF BUILDINGS

Work under this item shall conform to the requirements of Section 9.99 amended as follows:

9.99.03 – Construction methods: Add the following:

Testing for asbestos-containing materials and lead based paint will be performed by the Borough of Naugatuck. The Borough will be responsible for removing all asbestos-containing materials from the building. When all asbestos-containing materials have been removed from the building, the buildings will be turned over to the contractor.

The contractor shall be responsible for the collection of a complete building waste stream sample and analysis of that sample for lead following a Toxicity Characteristic Leaching Procedure (TCLP) extraction, prior to the removal of any waste from the site. The contractor shall assume the waste will not be classified as hazardous waste due to lead content. The contractor demolition and disposal methods and worker certifications and/or training shall comply with all local, state and federal regulations. The site shall be left as a level gravel area and no visible building waste is to remain.

The contractor may use the site for construction operations. The contractor shall name the property owner as additional insured on all insurance documents.

9.99.04 – Method of Measurement: Delete and replace with the following:

The removal and disposal of the building will be measure by the lump sum.

9.99.05 – Basis of Payment: Delete and replace with the following:

The contractor shall include in this lump sum price all benefits for easier access for bridge construction that would otherwise be reflected in lower unit costs of other items.

If the Town chooses to remove the building, this item will be paid at the contract Lump Sum price which shall include all materials, tools, equipment, and labor incidental thereto.

Additional cost for disposing of waste classified as hazardous will be paid as extra work. The contractor shall submit proof of his calculated bid cost of disposal. The extra work will be the additional cost associated with the disposal of the building waste stream as hazardous waste.

| Pay Item | |
|-----------------------|--|
| Disposal of Buildings | |

Pay Unit LS.