

Dry Wall Repair and Paint Project
Naugatuck Fire Dept.
41 Maple Street
Naugatuck, CT 06770
203-720-7082

Long term roof leaks caused ceiling and wall damage throughout second floor office area.

- An oil-based stain-blocking primer will be used for all water-stained areas.
- A latex based primer will be used on all non water-stained areas, including walls.
- Two coats of latex satin paint will be used on the walls and trim, colors to be determined by Chief.
- Two coats of latex flat white will be used on the ceilings.
- Dry wall to be repaired as needed.

The following eleven (11) areas/rooms are to be repaired and painted. All dimensions are approximate and need to be verified by bidder.

1. **Elevator Area:** Above stairs 156" X 44", landing area 120" X 88", outside door 24" X 41". Ceiling and wall damage and water stains.
2. **Hallway connector:** 53' X 74" arched, 2 Walls 53' X 8", above doorway 76" X 19", wall above doorway 74" arched. Multiple ceiling cracks.
3. **Secretary's Office:** Ceiling and walls of 11' X 10" room. Moderate ceiling and wall damage and water stains.
4. **Chief's Office:** Ceiling and walls of 20' X 11' room. Minor ceiling and wall damage and water stains.
5. **Utility Room:** Ceiling and walls of 8' X 8' room. Ceiling and wall damage and water stains.
6. **Deputy Chief's Office:** Ceiling and walls of 15' X 11' room. Minor ceiling and wall damage and water stains.
7. **Asst. Chief's Office:** Ceiling only of 11' X 8'5" room. Minor water damage.
8. **Storage Room:** Ceiling and walls of 6'6" X 7' room. Moderate ceiling and wall damage and water stains.
9. **A. Office waiting area:** 91" X 140", 30' X 46", 32' X 46" moderate ceiling and wall cracks and water stains, including all four corners beneath cupola.
B. Outside of Captain's Office: Ceiling and wall damage.
C. Outside of Asst. Chief's Office: Ceiling and wall damage.
10. **Interior hallway walls:** Repaint green area and above. (2) 9' X 16', (2) 9' X 8'.
11. **Copier room:** Ceiling and Walls of 11' X 8'6" room.